

NIQ/INKEL/EKM/2017-18/201

03/01/2018

**NOTICE INVITING QUOTATION****TOPOGRAPHICAL SURVEY WORKS FOR GOVERNMENT MEDICAL  
COLLEGE, WAYANAD**

Sealed quotations are invited by M/s INKEL Limited having its registered office at Door No. 7/473ZA – 5 & 6, 2nd Floor, Ajiyal Complex, Kakkanad, Cochin 682030, so as to reach the undersigned on or before **12/01/2018** up to 2.30pm for carrying out the work listed below. The quotations received will be opened at 3.00pm on the same day. The description of works to be carried out is attached along with this document. The rates quoted shall be final and all-inclusive and nothing extra will be paid on any account. The quotations for submission shall not be sent by post or courier.

**Specific Conditions:**

1. The intending bidders should have completed at least one work of similar nature during the last three years.
2. Quotation formats can be downloaded from our website [www.inkel.in](http://www.inkel.in)
3. The intending bidders should submit the copy of ESI & EPF registration details along with the quotation.
4. The contractor's rate must be firm and include the cost of transportation of materials to the site, all applicable taxes etc. **The rates quoted by the contractor shall be firm throughout the contract period and there shall be no upward revision of the rates quoted by the contractor for any reasons whatsoever.**
5. The contractor should carry out the survey with reference to an approved sketch of the plot issued from the Revenue department. Any irregularities / encroachments observed should be brought to the notice of the client with the help of a super – imposed drawing
6. The contractor shall carry out the topographical survey and preparation of plan / map of the entire area/areas indicated for the building and its allied structures.
7. The contractor shall carry out the bench mark by fly-leveling from the nearest available source as approved by the Engineer-in-Charge and establish the same on a permanent bench mark at a convenient location(s) at site as per the instructions of the Engineer-in-Charge.
8. In case of steep slopes and dense jungle etc where gridding is not possible, the method of survey, contour intervals etc shall be decided by the engineer-in-charge at site. Any unusual condition or formations on the ground, location of outcrops and springs/falls etc shall also be noted and plotted on the maps.

9. The contractor shall make all arrangements of men, material, instruments, surveyors, necessary records, field data etc. at the work site for checking of the work to the satisfaction of the Engineer-in-charge or his authorized representative during the progress and on successful completion of the work. The contractor shall intimate well in advance before final decamping from work site so that the final work can be inspected by the Engineer-in-charge.
10. The quantity mentioned in the BOQ is indicative only. The payment shall be based on the actual area as certified by INKEL.
11. The payment terms for the work shall be released within 30 days of receipt of drawings / reports and invoice for the completed work.
12. The duration of contract shall be 30 days from the award of work.

Authorized Signatory  
INKEL Limited  
Cochin - 30



# INKEL LIMITED

Issue No. / Date: 01/03.11.2016  
Revn. No. / Date:00

NOTICE INVITING QUOTATION

IL/ISO/PUR/11  
Page 1 of 2

**Project : GOVERNMENT MEDICAL COLLEGE WAYANAD**

**Name of Work - Topographical Survey Works for Government Medical College, Wayanad**

**Schedule of Quantities**

<i>Sl No.</i>	<i>Description</i>	<i>Unit</i>	<i>Qty</i>	<i>Rate (Rs.)</i>	<i>Amount (Rs.)</i>
1	Mobilization, clearing of bushes and minor obstructions, de – marking of permanent bench mark inside the property	LS			
2	Conducting topographic/land survey for the work and preparing suitable drawings of land - three sets of hard and soft (CAD) colour copies of drawings indicating existing roads, site boundary, existing building, trees, structures, posts (electric cables), wells, ponds, drains, water pipes etc with contours including spot levels (5m interval), road levels etc. complete as per direction of Engineer-in-charge.	Sqm	2,02,350.00		
<b>Grand Total</b>					

**Total (Rupees .....**  
**.....Only)**

Place:

Signature of the Contractor:

Date:

Name & Address with Seal: