

Issue No.00 / Date: 15-01-24
Rev. No.00/Date: NA

NOTICE INVITING QUOTATION

FORM#IL/QA/TEN/02
Page 1 of 8

Name of work : Operation and maintenance for Vellanad - Chettachal Road (21.90 km) for the year 2025-26 under Rehabilitation of State Highways and Major District Roads-Package B

INKEL LIMITED

1st Floor, Ajiyal Complex,
Kakkanad, Cochin – 682030
(Phone: 0484 - 2978101)

No. NIQ/INKEL/EKM/2025-26/207

Date: 25th July 2025

NOTICE INVITING QUOTATION

Name of Work: Operation and Maintenance of Vellanad - Chettachal Road (21.90 km) for the year 2025-26 under Rehabilitation of State Highways and Major District Roads-Package B

Sealed quotations are invited by INKEL Limited (on behalf of INKEL-EKK Roads Pvt Ltd), having its registered office at 1st Floor, Ajiyal Complex, Kakkanad, Cochin 682030, so as to reach the undersigned on or before **01/08/2025** up to 2.30pm for carrying out the Maintenance of Vellanad - Chettachal Road (21.90 km) for the year 2025-26. The quotations received will be opened at 3.30 pm on the same day. The description of works to be carried out is listed in the attached Bill of Quantities. The rates quoted shall be final and all-inclusive and nothing extra will be paid on any account.

Specific Conditions

- Rates quoted shall be inclusive of GST, PF, ESI, Insurance charges etc.
- Routine maintenance items are to be carried out at site on daily basis.
- Supply of labour for PMU is @ 5 Nos labour per day on all working days except Sundays.
- For Supply of labour, working time is from 8 am to 5: 30 pm.
- Accommodation & conveyance of labour is in Contractor scope.
- Safety of workers and surrounding shall be the responsibility of the Contractor.
- Necessary barricades, warning boards, etc are to be provided wherever required.
- Necessary tools and plants required for the work are to be provided by the Contractor.

1. Eligibility Criteria

The intending bidders should have at least one year experience in executing similar work in Highways (routine maintenance works in any National Highway, State Highway, Major District Road, Other District Roads, City Road) within the last 3 years. Experience certificate & Work orders issued by the Client /Govt /Semi Govt Agency shall be produced for this purpose. Bids of applicants without experience as mentioned above shall be summarily rejected.

2. Issue Of Quotation

The intending bidder, who has the requisite experience in this field can download the quotation form from our website ***www.inkel.in***

3. Item Rate Contract

This work shall be item rate contract inclusive of all taxes. The contractor's rate must be firm and include the cost of transportation of materials to the site.

Name of work : Operation and maintenance for Vellanad - Chettachal Road (21.90 km) for the year 2025-26 under Rehabilitation of State Highways and Major District Roads-Package B

4. Location of Site – Vellanad - Chettachal Road (21.90 km)

5. The intending bidders should visit the site before submission of quotation. For site visit, contact Ph- 8606974014

6. The successful bidder has to sign an agreement with M/s INKEL Limited on non-judicial stamp paper worth Rs.500/- within 7 days of receipt of the acceptance letter.

7. Performance Guarantee and Performance Security Deposit

Not Applicable

8. Period Of Construction

The Contract period is 12 months. The Contractor has to employ their resources and carry out the routine maintenance works throughout the period of 12 months.

The work items mentioned in the schedule are to be executed as per the approved Maintenance schedule and evenly over a period of 12 months.

Commencement of the work shall be considered from the 7th day of receipt of acceptance letter.

9. All Inclusive Rates

The contractor's rate must be firm and include the cost of transportation, loading/unloading of materials to the site, statutory levies & applicable cess etc. and the fixing or placing in position for which the item of work is intended to be operated. **The rates quoted by the contractor shall be firm throughout the contract period and there shall be no upward revision of the rates quoted by the contractor for any reasons whatsoever.**

The quantities indicated in Schedule of Quantities are tentative and may vary according to the site conditions.

10. Compensation For Delay

Not Applicable

11. Defects Liability Period

Not Applicable

12. Co-Ordination Of Work

The works are to be executed as per the direction of Road Maintenance Manager, INKEL Ltd. The Contractor has to employ necessary qualified supervisory staff minimum 1 (one) number full time at site for the entire contract period.

13. Insurance

Contractor has to obtain Workmen's Compensation policy for the workmen deployed for the O& M Period of 1 year.

Name of work : Operation and maintenance for Vellanad - Chettachal Road (21.90 km) for the year 2025-26 under Rehabilitation of State Highways and Major District Roads-Package B

14. EPF Contribution

The Contractor shall obtain EPF registration and ensure timely contribution as per the EPF Act, 1952, for all eligible workers. Proof of registration and monthly contribution shall be submitted to the Employer.

15. Water And Electricity

The contractor shall make his own arrangement for water and electricity required for the work. INKEL shall take no responsibility for the supply of either electricity or water.

16. The site should be kept clean and the surplus materials and unwanted debris should be removed / disposed to a proper place by the contractor or moved to a location as directed by INKEL.

17. Payment terms

All payments will be processed within 15 days thereof on submission of correct invoice and bill based on the joint site measurements, along with the payment certificate issued by Project Manager, INKEL. Also along with your Invoice you should submit details of proof of ESI& EPF remittance of the workers engaged for this work, ECR Challan, Wage Register, Muster Roll Copy register of each employees worked for the assignment as certified by Project Manager, INKEL.

Managing Director
INKEL Limited
Cochin –682030

Name of work : Operation and maintenance for Velland - Chettachal Road (21.90 km) for the year 2025-26 under Rehabilitation of State Highways and Major District Roads-Package B

SCHEDULE OF QUANTITIES

Sl No	Description	Unit	Qty	Rate	Amount
A	Maintenance works & PMU Labour				
1	VEGETATION CLEARANCE				
1.1	Clearing grass and removal of rubbish up to a distance of 50 metres outside the periphery of the area using Grass cutting machine	Sqm	370157.85		
1.2	Branch cutting of trees with tree cutter & Chainsaw etc upto a clearance of 5.5 meters from the road	No	167.00		
2	DRAINAGE WORKS				
2.1	Earthen drain cleaning and restoration by manual means	RM	15000.00		
2.2	Providing new earthen drain and retrenching of filled up earthen drains with JCB or equivalent.	RM	4500.00		
2.3	Supply of Tipper(150ft) for debris and surplus soil shifting	Day	5.00		
2.4	Cleaning of RCC drain under footpath by manual means, water jetting etc including removal of coverslab	RM	1400.00		
2.5	Removal and refixing of RCC cover slabs over drain including drain cleaning	Rm	4412.00		
2.6	Removal of earth from the choked RCC drain and disposing on the ROW edge manually	RM	12900.00		
2.7	Casting, conveyance and fixing of precast RCC cover Slab of M20 Grade for drain including steel reinforcement, aggregate size not exceeding 12 mm, true to line and grade, complete as per approved drawings and technical specifications. (Material, shuttering and Labour all complete)	Cum	3.00		

Name of work : Operation and maintenance for Velland - Chettachal Road (21.90 km) for the year 2025-26 under Rehabilitation of State Highways and Major District Roads-Package B

3	SHOULDER REPAIR WORKS				
3.1	Construction of earthen shoulders with approved outside borrow earth transporting to site, spreading, grading to required slope and compacted to meet requirement of table No. 300-2	Cum	100.00		
3.2	Construction of granular sub-base by providing graded Material for Road shoulder specifications as per PRICE item code : 3.18	Cum	25.00		
3.3	Plain/Reinforced Cement Concrete for road shoulder PCC M20 specification as per PRICE item Code : 12.8.B	Cum	5.00		
4	CULVERTS CLEANING				
4.1	Cleaning of culvert including catchpit, vegetation, vents and stream cleaning with necessary tools and Machineries etc.	Nos	106.00		
5	LAND SLIDE CLEARANCE				
5.1	Clearance of land slides in soil and ordinary rock by JCB or equivalent and disposal of the same on the valley side	Hrs	30.00		
6	REPAIR WORKS- STRUCTURES				
6.1	Earthwork excavation for foundation	Cum	21.60		
6.2	RR Masonry with Cement mortar (1:3)	Cum	5.00		
6.3	Pointing with Cement Mortar (1:3)	Sqm	60.00		
6.4	PCC 1:2:4	Cum	1.00		
7	PAINTING WORKS				
7.1.a	Supply of Enamel Paint of approved quality Brand Berger /Asian Paint with accessories like thinner etc for hand rail and road sign post painting(Berger Luxor/Asian Apcolite or equivalent)	Ltr	476.27		
7.1.b	Labour Charges for painting Hand rails with manual labour by cleaning the surface including the tools brush etc (Excluding cost of paint)	RM	5239.00		
7.1.c	Labour charges for painting Road sign posts with manual labour by cleaning the surface including the tools brush etc (Excluding cost of paint)	Per No	850.00		

Issue No.00 / Date: 15-01-24
Rev. No.00/Date: NA

NOTICE INVITING QUOTATION

FORM#IL/QA/TEN/02
Page 6 of 8

Name of work : Operation and maintenance for Velland - Chettachal Road (21.90 km) for the year 2025-26 under Rehabilitation of State Highways and Major District Roads-Package B

7.2	Supply of Exterior emulsion paint of approved quality Brand Berger/Asian paints with accessories like thinner etc for the Bridge & Culvert parapet, Km stones (Asian Apex/ Berger Weathercoat or equivalent)	Ltr	84.03		
7.3	Supply of Road Marking/Kerb marking paint (Golden yellow/ white / black) of approved quality thinner Brand Berger/Asian paints for Footpath kerb & Median kerbs(Berger Guideline RM 164/ Asian Apcotrak or equivalent)	Ltr	444.73		
7.4	Labour charges for painting exterior emulsion /Kerb marking paint with manual labour for the listed works by cleaning the surface including the tools brush etc (Excluding cost of paint)				
7.4.a	Culvert Parapets	Per No	106.00		
7.4.b	Painting Sub Km stone, Hectometre Stone, KM Stone & RBS Stone.- Labour Only.	Per No	1031.00		
7.4.c	Footpath Kerb	RM	4892.00		
7.4.d	Bridge Parapets / Bridge handrails	Per No	2.00		
8	ROAD FURNITURE REPAIR WORKS				
8.1	Refurbishment of existing signboards washing , correcting dislocation etc	Nos	780.00		
8.2	Repairing of Hand rails(including cutting, bending, welding, Painting and fixing) Labour with consumables	RM	625.00		
8.3	Supply and installation of Pearl grass or equivalent at damaged landscaping areas, including all labour and materials, with maintenance for three months, complete	Sqm	95.00		
8.4	Supply of labours for turf maintenance with tools. Manur etc.	Nos	96.00		
8.5	Supplying water through water tanker for landscape watering including cost of water , transport and labour	Ltr	150000.00		
8.6	Washing/ Cleaning of W beam Metal Beam crash barriers	RM	1060.00		
8.7	Washing/ Cleaning of pedestrian Handrails	RM	2600.00		
8.8	Fixing 3M brand reflective stickers on structures, Guard stone etc	RM	50.00		

Name of work : Operation and maintenance for Velland - Chettachal Road (21.90 km) for the year 2025-26 under Rehabilitation of State Highways and Major District Roads-Package B

8.9	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads on Bituminous Surface @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.	Sqm	Rate only		
-----	--	-----	-----------	--	--

9	FIXING OF ROAD SINAGES				
----------	-------------------------------	--	--	--	--

9.1	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign with 90cm size with 7years warranty manufactured as per IRC :67 made of Type IV micro prismatic grade sheeting vide clause 801.3.3 fixed over aluminium sheeting, 2 mm thick/ aluminium composit material sheeting 4 mm thick with suitable back supporting frame of MS angle 25x25x3 and supported on GI pipe pole 50mm NB confirming to IS 1239 firmly fixed to the ground by means of properly designed foundation with M 15 grade cement concrete min size 45 cm x 45 cm x 60 cm, 60 cm below ground level including painting all exposed surface with 2 coats of epoxy painting over epoxy primer and as per approved drawing and clause 801 including lettering symbols etc.	Nos	Rate only		
-----	--	-----	-----------	--	--

9.2	Providing and fixing object Hazard Marker	Nos	Rate only		
-----	---	-----	-----------	--	--

9.3	Direction and informatory board larger than 0.9 sqm area	Nos	Rate only		
-----	--	-----	-----------	--	--

9.4	Sheveron Board	Nos	Rate only		
-----	----------------	-----	-----------	--	--

9.5	Repair of footpath tiles / paver block including labor & material	Sqm	10.00		
-----	---	-----	-------	--	--

Name of work : Operation and maintenance for Velland - Chettachal Road (21.90 km) for the year 2025-26 under Rehabilitation of State Highways and Major District Roads-Package B

9.6	Providing and fixing reflective road studs (Raised Pavement Marker) of ' category A' made out of ASA/HIPS/ABS moulded body with shanks and conforming to ASTM D 4280, strong enough to support a load of more than 13.635 T when tested in accordance with ASTM D 4280, reflective panel confirming to ASTM D 788, and reflectivity conforming to clause 804.4. including installation, drilling, fixing with adhesive etc. with 2 years warranty for the road stud as well as for in field performance as per clause 804.7.3	Nos	Rate only		
9.7	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground/road level, all steel parts and fitments to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, 330 mm long complete as per clause 811.3	Rm	Rate only		
9.8	Supplying and installation of delineator (Road way indicators) posts 80- 100cm high above ground level, painted black and white in 15 cm wide strips, fitted with min. 80 x 100 mm rectangular or 75 mm dia circular retro reflectorised panels at the top with minimum visibility of 300m with provisions to prevent edge lifting and vandalisam, and conforming to clause 806 , IRC-79 and the drawings including fixing to ground (The deleniator shall be of approved type as per specification)	Nos	Rate only		
9.9	Routine Maintenance of LED solar street light including panel cleaning, battery water refilling. (Two times per year)	Nos	142.00		

Name of work : Operation and maintenance for Velland - Chettachal Road (21.90 km) for the year 2025-26 under Rehabilitation of State Highways and Major District Roads-Package B

9.10	Routine Maintenance of LED solar blinker including panel cleaning, battery water refilling. (Two times per year)	Nos	8.00		
9.11	Routine Maintenance of highmast light	Nos	5.00		
9.12	Routine maintenance of traffic signals (Aryanad Junction)	Nos	1.00		
9.13	Supply and Installation of blinker light battery-26 AH , EXIDE or equivalent	Nos	8.00		
9.14	Supply of 300mm Plastic 'High Visibility' colored traffic cones.	Nos	50.00		
9.15	Supply of Men at work board above 1 Sqm	Nos	4.00		
9.16	Providing and erecting a "W" metal beam crash barrier as per PRICE Code 8.23.A	RM	4.00		
10	SUPPLY OF EQUIPMENTS FOR O&M				
10.1	Supply of JCB for cleaning works	Hrs	33.00		
10.2	Supply of Tipper for cleaning works	Day	7.00		
10.3	Supply of Concrete Breaker	Day	10.00		
	Total Maintenance works (Civil)				
B	Part II : Supply Of PMU Labours				
1	Supply of Unskilled Labours for PMU with all necessary tools, PPE	Nos	1560.00		
	PMU Labour				
11	TESTING CHARGES & RENTALS				
11.1	Total testing rates for the Road Roughness Index test on Project Road by an agency approved by the Independent Engineer (two-lane road), including transportation, toll charges, and submission of the test report etc.- two lane road	KM	39.80		
11.2	Total testing charges for carrying out Benkelman Beam Deflection Test on Project Road by an agency approved by the Independent Engineer (two-lane road), including transportation, toll charges, and submission of the test report etc.- Two lane road	KM	19.90		
11.3	Rental charges for IE's Field Office-1500 Sqft	Monthly	12.00		

Issue No.00 / Date: 15-01-24
Revn. No.00/Date: NA

NOTICE INVITING QUOTATION

FORM#IL/QA/TEN/02
Page 10 of 8

Name of work : Operation and maintenance for Vellanad - Chettachal Road (21.90 km) for the year 2025-26 under Rehabilitation of State Highways and Major District Roads-Package B

C	Project Vehicle Running expenses				
1	Supply of Drivers for Project vehicle at RICK Ltd	Months	12.00		
2	Supply of diesel for Project vehicles	Ltr	1119.17		
3	Routine services & Repair charges for Vehicles	Ls	1.00		
Grand Total					-
Add GST 18%					-
Grand Total incl GST					-

Place:

Signature of the Contractor: