

Name of work: Restoration of road - KWA JJM Pipe laying works-Vellanad - Chettachal Road (CH 4+650 to 11+280) Luthergiri to Parandode.

INKEL LIMITED

1st Floor, Ajiyal Complex,
Kakkanad, Cochin – 682030
(Phone: 0484 - 2978101)

No. NIQ/INKEL/EKM/2025-26/215

Date: 20th February 2026

NOTICE INVITING QUOTATION

Name of Work: Restoration of road - KWA JJM Pipe laying works-Vellanad - Chettachal Road (CH 4+650 to 11+280) Luthergiri to Parandode.

Sealed quotations are invited by INKEL Limited (on behalf of INKEL-EKK Roads Pvt Ltd), having its registered office at 1st Floor, Ajiyal Complex, Kakkanad, Cochin 682030, so as to reach the undersigned on or before **27/02/2026** up to 2.30pm for carrying out the “Restoration of road -KWA JJM Pipe laying works-Vellanad-Chettachal Road (CH 4+650 to 11+280) Luthergiri to Parandode.” The quotations received will be opened at 3.00pm on the same day. The description of works to be carried out are detailed in the attached Schedule of Quantities. The rates quoted shall be final and all-inclusive and nothing extra will be paid on any account.

PAC – Rs. 37,46,730/- including GST

Scope of Work & Specific Conditions

- The scope of work is the restoration of damages to the road Vellanad Chettachal Road, Thiruvananthapuram due to the laying of utilities by Kerala Water Authority. The Contractor has to carry out the restoration works immediately after the utility laying works, as and when basis.
- Work front availability is subject to the progress of utility laying works by the Agencies. The Contractor has to carry out the repair works in parallel with the utility laying activities.
- The work is to be done under the Supervision and satisfaction of Independent Engineer (IE)/RICK Ltd.
- The measurements are to be get certified by IE and respective utility agency like KWA.
- If during the course of execution of contract, the performance of the contractor is not satisfactory, INKEL - EKK reserves the right to terminate the contract and engage any other agencies for the completion of the work.

1. Eligibility Criteria

The intending bidders should be a registered class ‘C’ contractor in Kerala PW. OR should have successfully completed similar works of minimum value ₹1.00 Crore during the last financial year.

2. Issue Of Quotation

The intending bidder, who has the requisite experience in this field, can download the document free of cost from our website www.inkel.in

3. Item Rate Contract

This work shall be item rate contract inclusive of all taxes. The contractor’s rates must be firm and include the cost of transportation of materials to the site.

Name of work: Restoration of road - KWA JJM Pipe laying works-Vellanad - Chettachal Road (CH 4+650 to 11+280) Luthergiri to Parandode.

4. **Location of Site**– Vellanad Chettachal Road, Thiruvananthapuram - (CH 4+650 to 11+280) Luthergiri to Parandode.
5. The intending bidders should visit the site before submission of quotation. For site visit, contact Ph-8606974014
6. The successful bidder has to sign an agreement with M/s INKEL Limited on non-judicial stamp paper worth Rs.500/- within 7 days of receipt of the acceptance letter.
7. **Performance Security Deposit**
A security deposit / retention amount at the rate of 2.5% of the value of work shall be deducted from the bills and shall be released upon completion of defects liability period.
8. **Period of Construction**
The Contract period is 6 months.
The work items mentioned in the schedule are to be executed as per the availability of work front over a period of 6 months.
9. **All Inclusive Rates**
The contractor's rate must be firm and include the cost of transportation, loading/unloading of materials to the site, statutory levies & applicable cess etc and the fixing or placing in position for which the item of work is intended to be operated. **The rates quoted by the contractor shall be firm throughout the contract period and there shall be no upward revision of the rates quoted by the contractor for any reasons whatsoever.**
The quantities indicated in Schedule of Quantities are tentative and may vary according to the site conditions.
10. **Compensation For Delay**
Not Applicable
11. **Defects Liability Period**
Any defect developed within the Defect Liability Period of twelve months will have to be rectified by the contractor at their own cost and in case the defects are not rectified by the contractor, INKEL - EKK or its authorized representative shall get the work done at the risk and cost of the contractor.
12. **Co-Ordination Of Work**
The works are to be executed as per the direction of Road Maintenance Manager, INKEL Ltd. The contractor must co-ordinate with other contractors involved in other related works within the site to minimize the disruption of continuous works.
13. **Insurance**
Contractor has to obtain Workmen's Compensation policy for the workmen deployed for the work.

Name of work: Restoration of road - KWA JJM Pipe laying works-Vellanad - Chettachal Road (CH 4+650 to 11+280) Luthergiri to Parandode.

14. Water And Electricity

The contractor shall make his own arrangement for water and electricity required for the work. INKEL shall take no responsibility for the supply of either electricity or water.

15. Statutory Payments

GST or any other taxes / statutory levies applicable to this contract will be deducted from each successive running bills and the final bill, as per the provisions in the act.

16. The site should be kept clean and the surplus materials and unwanted debris should be removed / disposed to a proper place by the contractor or moved to a location as directed by INKEL. Re-handling charges will not be allowed.

17. Payment terms

The payment of interim and final bills of the Contractor shall be paid only after receipt of funds from RICK Ltd. All payments will be processed on submission of correct invoice and bill based on the joint site measurements, along with the payment certificate issued by Project Manager, INKEL. Also along with your Invoice you should submit details of proof of ESI & EPF remittance of the workers engaged for this work, ECR Challan, Wage Register, Muster Roll Copy register of each employees worked for the assignment as certified by Project Manager, INKEL.

Managing Director
INKEL Limited
Cochin -682030

Issue No. 00 / Date: 15.01.2024

NOTICE INVITING QUOTATION

FORM#IL/QA/TEN/02

Name of work: Restoration of road - KWA JJM Pipe laying works-Vellanad - Chettachal Road (CH 4+650 to 11+280) Luthergiri to Parandode.

SCHEDULE OF QUANTITIES

Sl No	Item Description	Unit	Qty	Rate (Rs)	Amount (Rs)
1	Excavation for roadway in soil using manual means including loading in truck for carrying of cut earth to embankment site with all lifts and lead upto 1000 metres.	Cum	680.55		
2	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification Granular material	Cum	125.55		
3	Construction of granular sub-base by providing graded Material, mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with a motor grader on the prepared surface and compacting with plate compactor to achieve the desired density, complete as per clause 401 Grading-II - Plant Mix Method	Cum	420.00		
4	Plain/Reinforced Cement Concrete in Open Foundation complete as per Drawing and Technical Specifications; PCC Grade M25 - Using Concrete Mixer - (Without form work)	Cum	135.00		
5	Refixing of hand rail damaged while laying of KWA water line excavation	Metre	125.00		
6	Painting of hand rails with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. Two coats with suitable shade with ordinary paint of approved brand and manufacture	Sqm	20.00		
Total Amount in Rs (Excluding GST)					
GST @18%					
Total Amount in Rs (Including GST)					

Place:

Signature of the Contractor: